

ILC TDR Overview

ILC 技術設計書・概要

Akira Yamamoto (KEK)

山本 明 (KEK ILC 準備室)

the 1st ILC TDR Verification Working Group

第一回 ILC 技術設計書・検証作業部会

30 June, 2014



Outline

- Introduction
- Accelerator R&D: 加速器研究開発
- Accelerator Baseline Design : 加速器基本設計
- Detectors : 測定器
- Energy Staging : エネルギー・アップグレード
- Schedule : スケジュール
- Summary




ILC Technical Design Phase

ILC 技術設計段階・期間

1980' ~ Basic Study

2005 2006 2007 2008 2009 2010 2011 2012 2013 2014

2004



ILC-GDE

LCC

Ref. Design (RDR)

Tech. Design: TDP1

TDP 2


LHC

TDR completion




Selection of SC Technology

126 GeV



Higgs discovered



2012.12.15




2013.6.12



Important Energies in ILC

ILCにおける重要な衝突エネルギー

❖ Discovery of a 125 GeV Higgs has reinforced the importance of the ILC





Requirements from Physics


物理実験からの要求

● Basic requirements (基本要件) :

- Luminosity : $\int L dt = 500 \text{ fb}^{-1}$ in 4 years
- E_{cm} : **200 – 500 GeV, and the ability to scan**
- E stability and precision: $< 0.1\%$
- Electron polarization: $> 80\%$



● Extend-ability (エネルギー拡張性) :

- Energy upgrade: **500 \rightarrow 1,000 GeV**





ILC TDR Layout



Parameters	Value
C.M. Energy	500 GeV
Peak luminosity	$1.8 \times 10^{34} \text{ cm}^{-2}\text{s}^{-1}$
Beam Rep. rate	5 Hz
Pulse duration	0.73 ms
Average current	5.8 mA (in pulse)
E gradient in SCRF acc. cavity	$31.5 \text{ MV/m} \pm 20\%$ $Q_0 = 1E10$

ILC Scheme | © www.form-one.de



Preface: ILC TDR Configuration

TDR の構成

- **ILC Technical Design Report (Published, June, 2013)**

<https://www.linearcollider.org/ILC/Publications/Technical-Design-Report>

- Vol. 1. Executive Summary
- Vol. 2. Physics
- **Vol. 3, P1. Accelerator: R&D in the TD Phase**
- **Vol. 3, P2. Accelerator: Baseline Design**
- **Vol. 4. Detectors**
- (+) From Design to Reality

- **TDR Supporting Documents**

<https://www.linearcollider.org/ILC/Publications/Technical-Design-Report>

- Project Implementation Planning
- Cost Conversion Report
- Guide to the Cost Estimate
- List of signatures

- ILC TDR Value Estimate and Schedule (confidential documents)

- V. 6.0, April 13, 2013.


- Further details in ILC EDMS (confidential documents),

The screenshot displays a grid of document covers for the ILC TDR. The covers are arranged in two columns and four rows. The first row shows 'Volume 1 - Executive Summary' (9.5 MB) and 'Volume 2 - Physics' (9.5 MB). The second row shows 'Volume 3 - Accelerator' Part I: R&D in the Technical Design Phase (91 MB) and 'Volume 3 - Accelerator' Part II: Baseline Design (72 MB). The third row shows 'Volume 4 - Detectors' (66 MB) and 'From Design to Reality' (5.5 MB). The fourth row shows 'Supporting documentation' with links to 'Project Implementation Planning', 'Cost conversion report', 'Guide to the cost estimate', and 'List of signatories'. Each cover features the ILC logo and a stylized particle collision image.



ILC-TDR Vol. 3-I Accelerator R&D

Vol. 3-I, ILC 加速器技術開発



1. Introduction

2. Superconducting RF (SCRF) technology

1. Cavity field **gradient**
2. Cavity system test: **S1 Global**
3. Industrialization **E-XFEL**
4. ...
5. ...

focused

3. Beam Test Facilities

1. SCRF, Beam Acceleration: **FLASH, STF,**
2. Nano-beam handling : **ATF**
3. E- cloud mitigation: CESR-TA
4. ...
5. ...

focused

4. Accelerator Systems R&D

5. Conventional Facilities and Siting Studies

6. Post-TDR R&D (to be briefly reported)

1. **SCRF, ATF, ...**

Global Cooperation for Test Facilities

国際協力による加速器試験施設

TTF/FLASH (DESY) ~1 GeV
ILC-like beam ILC RF unit



DESY

INFN Frascati




DAΦNE (INFN Frascati)
kicker development
electron cloud

STF (KEK) operation/construction
ILC-like Cryomodule test: S1-Gloabal
SRF beam acceleration : QB, STF2



KEK, Japan



ATF & ATF2 (KEK)
ultra-low emittance
Final Focus optics, nano-beam
KEKB electron-cloud



CesrTA (Cornell)
electron cloud
low emittance

Cornell

FNAL



NML/ASTA facility
ILC RF unit test
Full-CM Test,
SRF beam acceleration, soon



Technical Highlight in TD Phase


技術設計段階での技術開発・ハイライト

- **SCRF Technology (超伝導・ビーム加速技術)**
 - Cavity: High Gradient R&D:
 - **35 MV/m** with 50% yield by 2010 , and 90% by 2012 (TDR)
 - Manufacturing with cost effective design
 - Cryomodule performance including HLRF, and LLRF
 - Beam Acceleration
 - **9 mA**: FLASH
 - **1 ms**: STF2 - Quantum Beam
- **Nano-beam handling (ナノビーム技術)**
 - ILC-like beam acceleration
 - Ultra-low beam emittance: Cesr-TA, ATF
 - Ultra-small beam size at Final Focusing: ATF2



Advantage of Superconducting RF

超伝導RF の特色・利点



❖ Ultra-high ($Q_0 = 10^{10}$):

- small surface resistance → almost zero power (heat) in cavity walls
- use relatively low-power microwave source to 'charge up' cavity (高い高周波電力効率)

❖ Long beam pulses (~1 ms)

- intra-pulse feedback (パルス中でのフィードバック制御、可)

❖ Larger aperture / smaller beam loss

- better beam quality with larger aperture - lower wake-fields (大口径→少ビームロス)

❖ Work necessary on engineering for:

- Cryomodule (thermal insulation)
- Cryogenics (冷却)
- Gradient to be further improved

Luminosity:

$$L \propto \frac{\eta P_{RF}}{E_{CM}} \sqrt{\frac{\delta_{BS}}{\epsilon_y}}$$

RF efficiency (points to η)

RF power / beam current (points to P_{RF})

Vertical emittance (tiny beams) (points to ϵ_y)

❖ Luminosity proportional to RF efficiency ILC

- ❖ (ルミノシティはRF効率に比例):
- ❖ for given total power (electricity bill !),
- ❖ ~160MW @ 500GeV

❖ Capable of efficiently accelerating high beam currents (大電流)

❖ Low impedance aids preservation of high beam quality (low emittance) (良質ビーム)

→ Ideal for Linear Collider



Global Plan for SCRF R&D

超伝導空洞技術開発タイムライン

Year	07	2008	2009	2010	2011	2012
Phase	TDP-1			TDP-2		
Cavity Gradient (電界) test to reach 35 MV/m	→ Yield 50%			→ Yield 90%		
Cavity-string to reach 31.5 MV/m, with one- cryomodule (システム)	Global effort for string assembly and test (DESY, FNAL, INFN, KEK)					
System Test with beam acceleration (ビーム)				FLASH (DESY) , NML/ASTA (FNAL) QB, STF2 (KEK)		
Preparation for Industrialization (工業化)				Production Technology R&D		
Communication with industry (企業との検討)	1 st Visit Vendors (2009), Organize Workshop (2010) 2 nd visit and communication, Organize 2 nd workshop (2011) 3 rd communication and study contracted with selected vendors (2011-2012)					



Progress in 1.3 GHz Cavity Production

1.3 GHz 超伝導加速空洞製造実績の進展

year	# 9-cell cavities qualified	Capable Lab.	Capable Industry
2006	10	1 DESY	2 ACCEL, ZANON
2011	41	4 DESY, JLAB, FNAL, KEK	4 RI, ZANON, AES, MHI ,
2012	(45)	5 DESY, JLAB, FNAL, KEK , Cornell	5 RI, ZANON, AES, MHI , Hitachi


- One Lab (2 vendor) in 2006, and 5 Lab (5 vendor) in 2012
may handle to fabricate 35 MV/m at Q= 8E9

- 6年間で、技術を保有する研究所、（製造会社）が1,(2) → 5 機関に、



Progress in SCRF Cavity Gradient

空洞製造・成功率の向上



Production yield:
94 % at > 35+/-20%
(目標の> 90 % を達成),

Average gradient:
37.1 MV/m

reached (2012)

電界性能幅 +/-20 % → 成功率 (歩留まり) ~10% 向上




DESY: FLASH


Cryomodule System Test

超伝導加速空洞・CMおよびビーム加速実証試験

- ❖ 1.25 GeV linac (TESLA-Like tech.)
- ❖ ILC-like bunch trains:
- ❖ 600 ms, **9 mA** beam (2009): ← ILC ビーム電流の実証
- ❖ 800 ms 4.5 mA (2012)
- ❖ RF-cryomodule string with beam → PXFEL1 operational at FLASH



XFEL Prototype at PXFEL1




KEK: SRF Test Facility (STF/STF2)

- ❖ S1-Global: completed (2010)
- ❖ Quantum Beam Accelerator (Inverse Laser Compton): 6.7 mA, **1 ms** ← ILC ビームパルス長の実証
- ❖ CM1 test with beam (2014 ~2015)
- ❖ STF-COI: Facility to demonstrate CM assembly/test in near future



S1 Global Cryomodule at STF:




FNAL: NML (New Muon Lab) / ASTA (Advanced Superconducting Test Accelerator)

- ❖ CM1 test complete
- ❖ CM2 operation (2013)
- ❖ CM2 with beam (soon)



CM1 at NML Facility:



2014.06.30

ILC TDR Overview